2026-BOYLAND COMMUNITY CENTER — 30600

444 Thomas Boyland St, Brooklyn, NY 11212

Change orders report generated by Tomasz Bartosiak (Elli NY Design)

Change Order 30600-0003 - Change Order based on ASI 22

Creator	Shalini Sangiliyandi (Elli NY Design)	**Total cost**	29,651.67 USD
Assignee	Shalini Sangiliyandi (Elli NY Design)	**Reason**	Design change
Status	Pending approval	**Reference number**	ASI 22
Due date	—	**Schedule impact?**	Yes
Responsible company	Elli NY Design	**Company address**	50-01 Metropolitan Ave, Ridgewood, NY
Description	Elli to provide material and labor to fabricate, finish, and install WD-4 millwork portals as shown in ASI 22.		

Response (rev.2)

Responded by	—	**Responded on**	—
Notes	—		
Attachments	—		

Cost (rev.2)

Submitted by	Shalini Sangiliyandi (Elli NY Design)	**Submitted on**	01/22/2026
Notes	(Material cost is calculated based on sheet count) Total F - 550 LF, To cover 550LF, 6 sheets of 1 1/4" 4x8 feet rift cut white oak with exposed edges.		
Backup documents	Estimate 117141 - Rift W Oak 30Pcs 1-14 x 4 x 8 .pdf, 2301 ASI 022_2025-12-23_Combined - 10 - INTERIOR ELEVATIONS - GIRLS CLUB CORRIDOR.pdf, 2301 ASI 022_2025-12-23_Combined - 6 - ELEVATOR INTERIOR CAB - PLANS, RCP'S & ELEVATIONS.pdf, 2301 ASI 022_2025-12-23_Combined - 9 - INTERIOR ELEVATIONS - MSC CORRIDOR.pdf, Solid Wood Reveal - Pricing Backup - ASI 22.pdf, Aluminum Angle - Pricing Backup - ASI 22.pdf		

Cost summary (USD)	
Original contract	0.00
Previously approved changes	0.00
Current contract	0.00
This change order	**29,651.67**
New contract with this change order	**29,651.67**

Submitter signature **Date**

Approver signature **Date**

Cost breakdown (rev.2)

Materials

#	ITEM NAME	QUANTITY	UNIT TYPE	UNIT COST (USD)	ITEM COST (USD)
1	Material to provide WD-4 (White Oak Veneer with Exposed Edges) portals around Elevators in 2nd Floor (Includes 20% Overage) - see quote attached as backup - 6 sheets	1.0	Lump sum	4,529.96	4,529.96
2	Aluminum Angles as per shown in detail A-560/7 (See backup for cost)	70.0	Each	81.70	5,719.00
3	Material to provide solid white oak reveal around Elevators in 2nd Floor (Includes 20% Overage) - see quote attached as backup	1.0	Lump sum	2,637.50	2,637.50
				MATERIALS	12,886.46

Labor

#	ITEM NAME	QUANTITY	UNIT TYPE	UNIT COST (USD)	ITEM COST (USD)
1	Shop Labor to cut WD-4 portal material to size (2 shop carpenters)	16.0	Hours	68.40	1,094.40
2	Shop Labor to spray wood surrounds and reveals (1 shop finisher)	16.0	Hours	77.55	1,240.80
3	Shop Labor to predrill, prepare and package materials (2 shop carpenter)	16.0	Hours	68.40	1,094.40
4	Field Labor to install WD-4 portals and reveals	64.0	Hours	124.50	7,968.00
				LABOR	11,397.60

Other

#	ITEM NAME	QUANTITY	UNIT TYPE	UNIT COST (USD)	ITEM COST (USD)
1	Delivery of Materials on Site	1.0	Lump sum	1,500.00	1,500.00
				OTHER	1,500.00

SUBTOTAL	**25,784.06**

Final Markups

#	ITEM NAME	APPLIED TO (USD)	PERCENTAGE	ITEM COST (USD)
1	Fabrication and Installation of Wood Surrounds	**Subtotal + Markups:** 25,784.06 USD	15.00%	3,867.61
			FINAL MARKUPS	3,867.61

THIS CHANGE ORDER **29,651.67**